



Gwasanaethau Dylunio Peirianegol

Sir Gâr
Carmarthenshire
County Council

Engineering Design Services

Adrian Harries B.Eng (Hons). C.Eng, M.I.C.E
Rheolwr Gwasanaethau Dylunio Proffesiynol
Professional Design Services Manager,
Adran Lle Seilwaith a Datblygiad Economaidd,
Bloc 1, Parc Myrddin, Waun Dew, Caerfyrddin
Sir Caerfyrddin SA31 1HQ
Department of Place, Infrastructure & Economic Development
Block 1, Parc Myrddin, Richmond Terrace, Carmarthen,
Carmarthenshire SA31 1HQ

Project
LLWYBRAU MWY DIOGEL YN Y GYMUNED
PUM HEOL 2025-2026

Title
CAMAU FERTIGOL ARFAETHEDIG

© Hawlfraint y Goron a hawliau cronfa ddata 2025 Arolwg Ordnans AC0000810849
© Crown copyright and database rights 2025 Ordnance Survey AC0000810849

REV	DATE	REVISION DESCRIPTION	REV BY	CHECKED	DATE CHD
Status YMGYNGHORI					
Made By	Date	Checked	Date	Authorised	Date
ME	17/06/25	VV	17/06/25	VP	17/06/25
Scale		Project no.			
1:2500		80/0040/557			
		Drawing no.		Revision	
		40/557 PC01		-	

ORIGINAL DRAWING FORMAT A3

TWMPATH ARAFU ESTYNEDIG

Lled llawn y ffordd fel arfer â brig gwastad o leiaf 6 metr i helpu cerbydau hir i symud yn fwy hwylus, ac uchder o 75mm (yn amodol ar yr amrywiadau a ganiateir yn y Rheoliadau Twmpathau Ffyrrdd, lle na fydd y twmpath yn uwch na 100mm)

TWMPATH Ffordd A BRIG CRWN

Twmpathau ffordd taprog (twmpathau nad ydynt yn mynd o un ochr y cwrbyn i'r llaill yn gyfan gwbl, gydag wyneb crwm. Lleiatfwm hyd 3.7 metr gydag uchder o 75mm (yn amodol ar y goddefiannau a ganiateir yn y Rheoliadau Twmpathau Ffordd, lle na fydd y twmpath yn uwch na 100mm)

- NODIADAU**
- Mae'r holl fesurau mewn metrau, oni nodir fel arall, ac nid yw'r darlun wrth raddfa.
 - Bydd y mesurau fertigol h.y. twmpath, yn cynnwys anwyddion rhybuddio a bydd y goleuadau stryd lleol yn cael eu huwchraddio.